

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS,
SECTOR-6, ROHTAK
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUVPA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 11.01.2024 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Providing and fixing Engraving Stone and Signboard at Main Gate of University Campus, DLCSUVPA, Rohtak. (Details of scope of work attached With the notice)	78,936/-	15 days

o/c ^{12/01/24}
SDE (Civil) 4/1/24
o

No. DLCSUPVA/UEW/ 7535 - 39

Dated: 4/1/24

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (Civil)
3. Supdt. (UEW)
4. JE (Civil)
5. IT Cell to upload on website please.

o/c ^{12/01/24}
SDE (Civil) 4/1/24
o



**DNIQ for Providing and fixing Engraving stone and Signboard at Main Gate of University
Campus, DLCSUPVA, Rohtak.
Approx. Amount:- Rs. 78,936/- (I/C GST)**

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor / Supplier	Amount
1.	HSR 5.1.2:- Dismantling dressed stone work ashlar face stone work, marble work or precast concrete work manually/ by mechanical means including stacking of serviceable and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: In cement mortar	0.311	Cum		
2.	HSR 5.45: - Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	4.08	Sqm		
3.	HSR 10.51: - Providing and fixing granite stone in all shades 15mm to 18 mm thick in skirting /dado, risers of steps, pillars and wall facing, laid in any pattern as specified over base of 12mm thick cement coarse sand mortar 1 :3 and jointed with white cement slurry mixed with pigment to match the shade of Granite including labour for fixing cramps pins and dowels etc.	4.08	Sqm		
4.	HSR 8.3: -Providing and fixing adjustable stainless steel cramps of approved quality, required shape and size, adjustable with stainless steel nuts, bolts and washer (total weight not less than 260 gms), for dry stone cladding fixed on frame work at suitable location, including making necessary recesses in stone slab, drilling required holes etc. complete as per direction of the Engineer-in-charge.	12.00	Nos.		
5.	NS Item:- Engraving stone:- INTEGRATED CAMPUS in capital word (word size 4.5"x1.5"x8mm depth). Engraving 4 Departments name in English and Hindi (Fine Arts, Urban Planning and Architecture, Film & Television, Design) (ललित कला, नगर नियोजन एवं वास्तुकला, फिल्म एवं टेलीविजन, डिजाइन) and capital word size 75 mm x 65 mm x 8mm depth and small word size 65mmx40mmx5mm depth Departments Logo (size 10"x6"x8mm depth) Govt. Logo (size 9"x11"x8mm depth)	42.00	Sft		

	University Logo size (220mmx220mm) with satisfaction of Engineer-in-Charge.				
6.	NS Item:- Supply and fixing of stainless steel retro signboard Stainless steel 304 grade frame hollow round pipe size 2" x3mm thick, 3mm thick ACP sheet and retro sheet. Sign of arrow size 2" thick with satisfaction of Engineer-in-Charge. As per IRC-67 of 2012.	30.00	Sft		
Total Amount (Including GST)					

Time Limit = 15 days.

Note:-

1. The work should be executed strictly as per the specification mentioned in DNIQ
2. Agency must quote the rates inclusive of GST.
3. Delay penalty will be as per U.A.C.

C
UEW

Balaji Siva
SDFCC

Arundhan
TECC
12/12/23

T.A to HVC

Arundhan
18/12/23

As per the instructions of T.A to HVC on file and as proposed by SDFCC, the DNIQ, is hereby approved. The same may be uploaded on university website.

SDFCC
(C)

DEO

Balaji Siva
4/1/24

Arundhan
22/12/23