

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS,
SECTOR-6, ROHTAK
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUVPA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 11.01.2024 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Repairing and painting of Room No. 13, FPA Building & FC Office of Visual Arts in DLCSUVPA, Rohtak. (Details of scope of work attached With the notice)	61,688/-	15 days

o/c Balwaj Singh
SDE (Civil)

No. DLCSUPVA/UEW/ 7567- 71

Dated: 5/1/24

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (Civil)
3. Supdtt. (UEW)
4. JE (Civil)
5. IT Cell to upload on website please.

Parvati
6/1/24

o/c Balwaj Singh
SDE (Civil)



**DNIQ for Repairing and painting of Room No. 13, FPA Building & FC Office of Visual Arts in
DLCSUPVA, Rohtak.**

Approx. Amount:- Rs. 61,688/- (I/C GST)

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor/ Supplier	Amount
1.	HSR 5.16.1:- Dismantling wood work in frames, trusses, purlins and rafters up to 10 metres span and 5 metres height including stacking the material within 50 metres lead: Of sectional area 40 square centimetres and above	5.72	Cum		
2.	HSR 11.58: - Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get an even and smooth finish including cost and carriage of all material, labour charges, scaffolding, sundries etc. complete.	52.61	Sqm		
3.	HSR 30.25.1:- Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade: Old work (one or more coats)	121.72	Sqm		
4.	HSR 30.28.1:- Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade, One or more coats on old work	15.61	Sqm		
5.	HSR 10.63.2: - Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	36.78	Sqm		
6.	HSR 10.67.2:- Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	2.91	Sqm		
				Total Amount (Including GST)	

Time limit = 15 days.

Note:-

- The work should be executed strictly as per the specification mentioned in DNIQ
- Agency must quote the rates inclusive of GST.
- Delay Penalty will be as per UAC.

~~Signature~~
to
SDE (C)

Approved
15/12/23
C
DEW

Balbir Singh
SDE (C) 14/12/23

Signature
TECO

