

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS,
SECTOR-6, ROHTAK
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby **re-invited** for and on behalf of Registrar DLCSUVPA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 23.01.2024 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Providing and fixing of tiles in Girls Hostel, VC Office and Miscellaneous work in Registrar Office in DLCSUVPA, Rohtak. (Details of scope of work attached With the notice)	71,832/-	10 days

est
SDE (Civil)

No. DLCSUPVA/UEW/ 7651-55

Dated: 16/1/24

Copy of the above is forwarded to the following for information and necessary action:-

- ✓ 1. Accounts Officer/ Nominee
2. SDE (Civil)
3. Supdtt. (UEW)
4. JE (Civil)
5. IT Cell to upload on website please.

Balwinder
SDE (Civil)

DNIQ for Providing and fixing of tiles in Girls Hostel, VC Office and miscellaneous work in Registrar Office in DLCSUPVA, Rohtak.
Approx. Amount = Rs. 71,832/-

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor / Supplier	Amount
1.	HSR 10.62:- Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1 :3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	34.75	Sqm		
2.	HSR 10.63.2:- Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	2.60	Sqm		
3.	HSR 10.50.1: Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1 :4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent. (Labour Rate)	0.691	Sqm		
4.	HSR 12.19.2.2.1:- Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws: With ISI marked stainless steel butt hinges of Second class teak wood	6.90	Sqm		
5.	HSR 12.45:- Providing and fixing 18 mm thick,	3.65	Mtr.		

	150 mm wide pelmet of coir veneer board ISI marked IS : 14842, including top cover of 6 mm coir veneer board, nickel plated M.S. Pipe 20 mm dia. (heavy type) curtain rod with nickel plated brackets, including fixing with 25x3 mm M.S. Flat 10 cm long fixed to pelmet with Hollock wood cleats of size 100 mm x 40 mm x 40 mm on both inner side of pelmet and rawl plugs 75 mm long etc. all complete.				
6.	HSR 11.76 + 11.77 + 11.78:- Preparation of ply wood surface for painting including sand papering the surface and applying filling with approved quality filler consisting of white lead, linseed oil, varnish and chalk mitti including finishing the surface to required finish complete. HSR 11.77: Applying pink primer or aluminium priming coat on wood work including preparation of surface, Knotting and stopping etc., HSR 11.78: Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	13.80	Sqm		
7.	NS Item: - Providing and fixing of privacy glass film, Make- ELECSA, 1 way perforated vinyl privacy window film adhesive glass wrap roll window film. Colour - white and black, Cartoon character - Bubble	119.31	Sft		
8.	NS Item:- Providing and fixing of white colour cloth curtain good quality size 8'x4', Make:- Décor 48"	4.00	Nos.		
Total Amount (Including GST)					

Time Limit: 10 Days

Note:-

1. The work should be executed strictly as per the specification mentioned in DNIQ
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.