DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS, SECTOR-6, ROHTAK NOTICE INVITING QUOTATIONS

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUVPA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated <u>26.02.2024</u> at <u>3:00 PM</u>. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Replace the Window of Server Room of Mini-Auditorium in FTV Department,	42,693/-	10 Days
DLCSUPVA, Rohtak (Details of scope of work attached With the notice)		

halles in

No. DLCSUPVA/UEW/ 7861 - 65

Dated: 19/2/24

Copy of the above is forwarded to the following for information and necessary action:-

- 1. Accounts Officer/ Nominee
- 2. SDE (Civil)
- 3. Supdtt. (UEW)
- 4. JE (Civil)
- 5. IT Cell to upload on website please.

SDE (Civil) 19/24

DNIQ for Replace the Window of Server Room of Mini-Auditorium in FTV Department, DLCSUPVA, Rohtak.							
Sr. No.	Approx. Amount = Rs. Description	42,693/- Qty.	Unit	RATE with taxes to be Quoted by Contractor / Supplier	Amount		
1.	HSR 5.49:- Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material within 50 meters lead as directed by Engineer-incharge	4.60	Sqm				
2.	HSR 12.134.3:- Two track two panels sliding window made of (big series) frame 67 x 50 mm & sash 46 x 62 mm both having wall thickness of 2.3 ± 0.2 mm and single glazing bead / double glazing bead of appropriate dimension. (Area of window above 1.75 sqm up to 2.50 sqm). Make:- Fenesta/Aluplast/ Classic/ AIS/ Syntex/ Vekancl / Jayna	4.60	Sqm				
3.	HSR 12.138:- Providing and fixing casement handle made of zinc alloyed (white powder coated) for uPVC casement window with necessary screws etc. complete. Make:- Rotto/ Door set/ Kinlong	4.00	Nos.				
4.	HSR 12.177.1: Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge. With toughened glass panes of 6 mm thickness (weight not less than 15 kg/sqm), Make:- Saint Gobain/ Gold Plus / Bharat Glass/ Viracon/	9.20	Sqm				

Time Limit: 10 Days

Modiguard

Note:-

- 1. The work should be executed strictly as per the specification mentioned in DNIQ
- 2. Agency must quote the rates inclusive of GST.
- 3. Delay Penalty will be as per UAC.

Total Amount (Including GST)