

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS,
SECTOR-6, ROHTAK
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUPVA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 01.05.2024 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Painting of Indication board at outer corner of Boundary wall of DLCSUPVA, Rohtak. (Details of scope of work attached With the notice)	7,615/-	10 Days

Balwinder Singh
SDE (Civil)

No. DLCSUPVA/UEW/ 8228-32

Dated: 24/4/24

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (Civil)
3. Supdt. (UEW)
4. JE (C)
5. IT Cell to upload on website please.

Balwinder Singh
SDE (Civil)

**DNIQ for the work of Painting of Indication board at outer corner of Boundary wall of DLCSUPVA,
Rohtak.**

Approx. Amount = Rs. 7,615/-

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor/ Supplier	Amount
1.	HSR 34.3:- Printing new letter and figures of any shade with synthetic enamel paint black or any other approved colour to give an even shade. Dada Lakhmi Chand State University of Performing & Visual Arts Department of Design Department of Film & Television Department of Visual Arts Department of Urban Planning and Architecture Department of Acting Word size height 8" (20 cm)	3576.00	Cm		
2.	HSR 11.78: - Painting two coats excluding priming coat with synthetic enamel paint in all shades on new wood work or metallic or plastered or concrete surfaces to give an even shade.	39.61	Sqm		
3.	HSR 30.94:- Providing and fixing double scaffolding system (cup lock type) on the exterior side of building/structure, up to 25 metre height, above ground level, including additional rows of scaffolding in stepped manner as per requirement of site, made with 40mm dia. M.S. tube, placed 1.5 metre centre to centre, horizontal & vertical tubes joint with cup & lock system with M.S. Tubes, M.S. tube challis, M.S. clamps and staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for execution of work of cleaning and/ or pointing and/ or applying chemical and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connecting with the building etc., wherever required, if feasible, for inspection of work at required locations with essential safety features for the workmen etc., complete as per directions and approval of Engineer-in-charge. Note: - (1) The elavational area of the scaffolding shall be measured for payment purpose. (2) The payment will be made once only for execution of all items for such works. (3) This item to be used for maintenance work judicially and where necessary deduction for scaffolding in the existing item is to be done.	18.12	Sqm		
Total Amount (Including GST)					

Time Limit: 10 Days

Note:-

1. The work should be executed strictly as per the specification mentioned in DNIQ
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.

