

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS,  
SECTOR-6, ROHTAK  
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUPVA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 25-6-24 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Cleaning sewerage line of girls hostel And adjacent vice-chancellor residence Sewerage line alongwith supply of 1 no. Sewerage submersible pump for DLCSUPVA Rohtak.	80900.00	07 DAYS

**(Details of scope of work attached  
With the notice)**


  
Estate Officer

No. DLCSUPVA/UEW/ 8636-40

Dated: 19/6/24

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. Estate Officer
3. Supdtt. (UEW)
4. JE (M)
5. IT Cell to upload on website please.

  
Estate Officer



**DNIQ for Cleaning sewerage line of Girls Hostel and adjacent Vice-Chancellor Residence sewerage line alongwith Supply of 1 no. sewerage Submersible Pump for DLCSUPVA, Rohtak. Approx. Amount:- 80,900/- (I/C GST)**

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor / Supplier	Amount
1.	HSR 21.103.1:- Job work for cleaning of sewer lines by bucket type sewer machine including cost of diesel/lubricant complete in all respect. 200 mm i/d	210	Meter		
2.	HSR 21.104.1: - SITC of sewage submersible motor pumping set non-clog for sewerage head 10 M (supply of submersible pump only) Make:- KSB, CRI, Crompton Greaves, LUBI, Kirloskar	01	No.		
3.	Flat submersible cable 4sqmmx 3 core copper Make: - Havells, Polycab, Plaza	30	Mtr.		
4.	Direct online starter (2 HP) for single phase motor make :- havells , l&t (2 hp capacity , with 20 ampere contactor , 13.2 A -20 A Overload relay with complete metal body confirms to IS/IEC 60947-4-1)	01	No.		
<b>Total Amount (Including GST)</b>					

**Time Limit: 07 Days**

**Note:-**

1. The work should be executed strictly as per the specification mentioned in DNIQ.
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.

*Approved. The DNIQ may be approved please.*

*[Signature]*  
15/06/24  
UAS

*[Signature]*  
19/06/24

*[Signature]*  
08/06/24

*E.O.*