

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL ARTS,  
SECTOR-6, ROHTAK  
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUVPA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 01.07.2024 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

Description	App-Amt.	Time Limit
Construction of Platform for Selfie Statue in front of Common Auditorium, DLCSUPVA, Rohtak <b>(Details of scope of work attached With the notice)</b>	19,175/-	15 Days

*Balkrishna*  
SDE (Civil) 24/6/24

No. DLCSUPVA/UEW/ 8670-74

Dated: 24/6/24

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (Civil)
3. Supdt. (UEW)
4. JE (Civil)
5. IT Cell to upload on website please.

*Balkrishna*  
SDE (Civil) 24/6/24



DNIQ for construction of Platform for Selfie Statue in front of Common Auditorium, DLCSUPVA, Rohtak.					
Approx. Amount: - 19,175/- (I/C GST)					
Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor/ Supplier	Amount
1.	HSR 4.14.1:- Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift up to 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil.	3.73	Cum		
2.	HSR 7.20.1:- Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement: 4 coarse sand)	1.71	Cum		
3.	HSR 6.1.2:- Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	2.72	Cum		
4.	HSR 11.8.1:- 12 mm cement plaster of mix : 1 :4 (1 cement: 4 coarse sand)	2.04	Sqm		
Total Amount (Including GST)					

**Time Limit: 15 Days**

**Note:-**

1. The work should be executed strictly as per the specification mentioned in DNIQ.
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.