

**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL  
ARTS, SECTOR-6, ROHTAK  
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUPVA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 19/5/25 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.

| Description   | App-Amt. | Time Limit |
|---|----------|------------|
| Chipping of unsound / weak concrete material from slabs, beams, columns etc. in DLCSUPVA, Rohtak.<br><b>(Details of scope of work attached with the notice)</b> | 95,996/- | 90 Days    |

No. DLCSUPVA/UEW/ Eo 191-95

*[Signature]*  
SDE (Civil)/E.O.

Dated: 10/5/25

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (C)/E.O.
3. Supdtt. (UEW)
4. JE (C)
5. IT Cell to upload on website please.

*[Signature]*  
11/5/25

*[Signature]*  
SDE (Civil)/E.O.  
*[Signature]*

**DNIQ for Chipping of unsound / weak concrete material from slabs, beams, columns etc. in DLCSUPVA, Rohtak.**

**Approx. Amount: - Rs. 95,996/- (I/C GST)**

| Sr. No.                             | Description   | Qty.   | Unit | RATE with taxes to be Quoted by Contractor/ Supplier | Amount |
|-------------------------------------|---|--------|------|--|--------|
| 1.                                  | HSR 31.2.1: - Chipping of unsound/weak concrete material from slabs, beams, columns etc. with manual Chisel and/ or by standard power-driven percussion type or of approved make including tapering of all edges, making square shoulders of cavities including cleaning the exposed concrete surface and reinforcement with wire brushes etc. and disposal of debris for all lead and lifts all complete as per direction of Engineer-In-Charge. 75mm average thickness.   | 519.75 | Sqm  |  |        |
| 2.                                  | HSR 30.93: - Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube Challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it thereafter. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer-in-charge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.<br>Note: - This item to be used for maintenance work judiciously and where necessary deduction for scaffolding in the existing item is to be done. | 132.89 | Sqm  |  |        |
| 3.                                  | HSR 5.1.2: - Dismantling dressed stone work ashlar face stone work, marble work or precast concrete work manually/ by mechanical means including stacking of serviceable and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge: In cement mortar  | 8.06   | Sqm  |  |        |
| 4.                                  | HSR 3.1.1: - Loading, Unloading, and Carriage of Materials. Lime, moorum, building rubbish. Lead upto 1 Km  | 68.09  | Cum  |  |        |
| <b>Total Amount (Including GST)</b> |   |        |      |  |        |

**Time Limit: 90...Days**

**Note:-**

1. The work should be executed strictly as per the specification mentioned in DNIQ
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.