

DNIQ for Supply and erection of E.I. item in open Gym in Residential Complex and supply of E.I. material for Girls Hostel, FTV Department & Design Department, PLCSUPVA, Rohtak.					
App. Amount = Rs. 67,190/-					
Sr. No.	Description	Qty.	Unit	RATE to be Quoted by Contractor/ Supplier	Amount
1.	HSR 23.4.1.3: - Wiring for Light/Fan/call bell point with modular type switch/socket and GI box, Modular type face plate etc. in 1.5 sqmm FRLS PVC insulated copper conductor cable in 1.6 mm thick PVC conduit pipe. Group C (for open Gym Residential Complex)	06	Nos.		
2.	HSR 23.3.6.2: - Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in PVC Conduit etc. as required. 1 run of Size 2.50 Sqmm(1.1.80mm) (for open Gym Residential Complex)	30	Mtr.		
3.	HSR 23.4.4.3: - Wiring in PVC conduit system for 3-pin 5amp. Plug point by using 2 no 1.5 sqmm FRLS copper wire and 1 no 1.5 Sqmm FRLS copper wire , including providing 1 no 5/6 Amp 3/5 pin Modular type socket and 1 no 5/6 Amp Modular type switch required GI Box, modular face plate etc. complete as required. Group C(for open Gym Residential Complex)	01	No.		
4.	HSR 23.7.6.2: - Supply and erection of PVC CONDUIT ISI marked (Medium) recessed in wall/ceiling etc. including the cost of PVC bends, inspection boxes, iron hooks and cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. PVC pipe of 25 mm dia. (for open Gym Residential Complex)	30	Mtr.		
5.	HSR 23.22.4.1: - Supply and erection of double door sheet steel enclosure distribution board suitable for MCBS and ELCBS etc. recessed in wall including bonding to earth with all labour and material required to complete the job in all respect up to the entire satisfaction of the Engineer-in-Charge of the work. SPN DB Double Door 4 way (2 incoming and 2 outgoing) (for open Gym Residential Complex)	01	No.		
6.	HSR 23.22.5.1: - Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections: 6 amp. to 32 amp Single Pole (for open Gym Residential Complex)	02	Nos.		
7.	HSR 23.22.5.3: - Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections: 6 amp. to 32 amp Double POLE (for open Gym Residential Complex)	01	No.		
8.	Supply of LED light 4 feet 20 watt, Make: - Havells, Crompton, Bajaj	40	Nos.		
9.	Supply of Electronic Chowk 40 watt for Tube Light, Make- Anchor, Phillips, Bajaj (FTV Deptt.)	90	Nos.		
10.	Supply of Fan Capacitor 3.5 MFD, Make- Tibcon (for Girls Hostel & University Campus)	100	Nos.		
11.	Supply of Modular Fan Regulator 2M for Girls Hostel, Make- Greatwhite	30	Nos.		
12.	Supply of Modular Switch 6 Ampere, Make- Greatwhite, Anchor for Girls Hostel	20	Nos.		
13.	Supply of Modular Socket 6 Ampere, Make- Greatwhite, Anchor for Girls Hostel	20	Nos.		
14.	Supply of Modular Switch 16 Ampere, Make- Greatwhite, Anchor for Girls Hostel	10	Nos.		
15.	Supply of Modular Socket 16 Ampere, Make- Greatwhite, Anchor for Girls Hostel	10	Nos.		
16.	Supply of Combined Box 16 Ampere, Make- Greatwhite, Anchor for Girls Hostel	10	Nos.		
17.	Supply of PVC Tape Roll, Make- Anchor, Steelgrip	30	Nos.		
18.	LED bulb 26 watt for street light, Make- Syska, Panasonic, Orient for Residential Complex	10	Nos.		
19.	Supply of Remote Bell, Make- Anchor, Cona	04	Nos.		
20.	Supply of Batton Holder, Make- Anchor, Girish (for Girls Hostel)	30	Nos.		
				Total Amount (Including GST)	

Note:-

1. Agency must quote the rates inclusive of GST.

NOTICE

PLCSUPVA, ROHTAK DNIQ	
Name of Work:	DNIQ for Supply and erection of E.I. item in open Gym in Residential Complex and supply of E.I. material for Girls Hostel, FTV Department & Design Department, PLCSUPVA, Rohtak.
Cost:	Rs. 67,190/-
Time limit	21 Days
Quotation to be received through email on (uew@plcsupva.ac.in) till 11.00 AM on dated 17-10-2022.	