


**DADA LAKHMI CHAND STATE UNIVERSITY OF PERFORMING AND VISUAL  
ARTS, SECTOR-6, ROHTAK  
NOTICE INVITING QUOTATIONS**

Sealed percentage/item rate quotations are hereby invited for and on behalf of Registrar DLCSUVPA, Rohtak for below noted work from the suppliers/Agencies/Contractors of Haryana PWD B&R, Public Health, Central PWD, H.U.D.A & Municipal corporation on plain paper on dated 01.09.2025 at 3:00 PM. Quotations will be opened at the same date and same time in the presence of quotationers or their representative who may like to be present at that time. All rate should be quoted including GST.


Description	Time Limit
Providing and fixing of 45 nos. computer point in Meeting Hall, 2nd Floor, Design Department, DLCSUPVA, Rohtak. (Details of scope of work attached with the notice)	10 Days

No. DLCSUPVA/UEW/ 601-05

  
Estate Officer  
Amr 35/E1  
Dated: 25/8/25

Copy of the above is forwarded to the following for information and necessary action:-

1. Accounts Officer/ Nominee
2. SDE (Electrical)
3. Supdtt. (UEW)
4. JE (E)
5. IT Cell to upload on website please.

  
Estate Officer  
Amr 35/E1

**DNIQ for providing and fixing of 45 nos. computer point in Meeting Hall, 2nd Floor, Design Department,  
DLCSUPVA, Rohtak.**

Sr. No.	Description	Qty.	Unit	RATE with taxes to be Quoted by Contractor/ Supplier	Amount
1.	HSR 23.7.6.2: Supply and erection of PVC CONDUIT ISI marked (Medium) recessed in wall/ceiling etc. including the cost of PVC bends, inspection boxes, iron hooks and cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. PVC pipe of 25 mm dia. Note: The rates worked out for items 23.1 to 23.7 and their sub-items are by considering recessed conduit wiring. These rates may be reduced by 15% wherever surface conduiting wiring is required to be done as per directions of Engineer-in-Charge.	150.00	Mtr.		
2.	HSR 23.7.6.3: Supply and erection of PVC CONDUIT ISI marked (Medium) recessed in wall/ceiling etc. including the cost of PVC bends, inspection boxes, iron hooks and cement concrete etc. complete in all respect up to the entire satisfaction of Engineer-in-Charge of work. PVC pipe of 32 mm dia. Note: The rates worked out for items 23.1 to 23.7 and their sub-items are by considering recessed conduit wiring. These rates may be reduced by 15% wherever surface conduiting wiring is required to be done as per directions of Engineer-in-Charge.	10.00	Mtr.		
3.	HSR 23.8.10.5: Providing and fixing GI concealed sheet metal boxes with inner and outer face plate including concealing the box in wall and fixing in position with inner plate and face plate with all labour and material required for the job complete in all respects. 8 Modules	45.00	Nos.		
4.	HSR 23.8.11.1: Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connections. complete in all respect. 5 amp 1 way switch	90.00	Nos.		
5.	HSR 23.8.11.4: Providing and fixing modular type accessories of approved make in existing box including fixing and making necessary connections. complete in all respect. 5 amp Socket	135.00	Nos.		
6.	HSR 23.5.6.2: Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in existing MS/PVC Conduit etc as required. 1 run of Size 2.50 Sqmm(1.1.80mm)	450.00	Mtr.		
7.	HSR 23.22.4.5: Supply and erection of double door sheet steel enclosure distribution board suitable for MCBS and ELCBS etc. recessed in wall including bonding to earth with all labour and material required to complete the job in all respect up to the entire satisfaction of the Engineer-in-Charge of the work. TPN DB Horizontal type Double Door 4 way ( 8 incoming and 3phase*4 outgoing)	1.00	No.		
8.	HSR 23.22.5.1: Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections: - 6 amp. to 32 amp Single Pole	12.00	Nos.		
9.	HSR 23.22.5.8: Supply and erection of miniature circuit Breaker 240/415 V in the existing distribution board including making necessary connections: - 40 amp to 63 amp. MCB's FOUR POLE	1.00	No.		
10.	HSR 23.5.6.4: Wiring main and sub mains in two single core for phase and neutral wire and one single core for earth wire PVC insulated Copper conductor cable 1100 Volts grade in existing MS/PVC Conduit etc as required. 1 run of Size 6 Sqmm(1/2.80mm)	70.00	Mtr.		
Total Amount (Including GST)					

**Time Limit: 10 Days**

**Note:-**

1. The work should be executed strictly as per the specification mentioned in DNIQ.
2. Agency must quote the rates inclusive of GST.
3. Delay Penalty will be as per UAC.